PLUMBING SPECIFICATIONS

15055 - BASIC PIPING MATERIALS AND METHODS

- CORE CUT ALL PIPE PENETRATION OF EXISTING MASONRY OR CONCRETE WALLS AND FLOORS. SLEEVE ALL PENETRATIONS THROUGH NEW WALLS AND FLOORS. SEAL ALL PENETRATIONS WATER TIGHT WITH SILICONE SEALANT. USE FIRE RATED SEALANT (3M "FIRE BARRIER" OR EQUAL) FOR 1 HOUR OR 2 HOUR PENETRATIONS.
- CAULK AROUND ALL PIPING THAT PASSES THROUGH FIRE-RATED PARTITIONS WITH A NON-HARDENING CAULKING SIMILAR TO 3M "FIRE BARRIER".
- 3. SEAL ALL PIPING THROUGH WALLS AIR TIGHT.

15242 - VIBRATION ISOLATION AND SEISMIC

- 1. ALL PLUMBING EQUIPMENT AND PIPING MUST BE VIBRATION ISOLATED AND SEISMICALLY BRACED FOR THE SITE SPECIFIC SEISMIC DESIGN CATEGORY AND SEISMIC USE GROUP, IN ACCORDANCE WITH THE LATEST ADOPTED EDITIONS OF THE BUILDING CODES AND ASHRAE. PROVIDE SEISMIC PRODUCTS BY AMBER-BOOTH OR MASON INDUSTRIES.
- 2. IN GENERAL, PROVIDE SPRING MOUNTS TO ATTENUATE LOW FREQUENCY SOUND AND VIBRATION. PROVIDE NEOPRENE PADS TO ATTENUATE HIGH FREQUENCY SOUND
- 3. VIBRATION: SEISMIC BRACING/MOUNTING CAN BE COMBINED WITH VIBRATION ISOLATION AS APPLICABLE.
- 4. CONTRACTOR MANUFACTURED SEISMIC BRACING/RESTRAINT METHODS ARE NOT ACCEPTABLE.
- 5. PROVIDE A SIGNED AND STAMPED LETTER FROM A PROFESSIONAL ENGINEER CERTIFYING THAT THE SUPPLIED PRODUCTS ARE CORRECT FOR THE APPLICATION AND THAT THE INSTALLATION IS IN COMPLIANCE WITH ALL APPLICABLE CODES.

15250 - INSULATION

- PIPE INSULATION: SNAP-ON GLASS FIBER TYPE WITH VAPOR JACKET. SEAL ALL ENDS AND JOINTS TO PROVIDE A COMPLETELY SEALED SYSTEM. ALTERNATIVELY, FOR INTERIOR WATER PIPING, USE FLEXIBLE UNICELLULAR ASTM 534 TYPE 1 INSULATION. USE 1" THICKNESS FOR PIPE UP TO 2" AND 1-1/2" FOR PIPE OVER 2"ø
- PROVIDE ADA COMPLIANT FIXTURES WITH SNAP ON ADA ARTICLE 4.19 22FF COMPLIANT WHITE INSULATION. TRUEBRO LAV GUARD, BASIN GUARD OR LAV SHIELD.

15411 - WATER DISTRIBUTION PIPING

- ALL ABOVE GROUND HOT AND COLD WATER PIPING: ASTM B 88 TYPE "L" COPPER. WITH WROUGHT COPPER FITTINGS AND SOLDERED WITH 95-5 TIN-ANTIMONY SOLDER.
- INSTALL PIPE HANGERS WITH THE FOLLOWING MINIMUM ROD SIZES AND MAXIMUM SPACING. UPON COMPLETION OF HANGER INSTALLATION, ALL ADJUSTMENTS HAVING THE POSSIBILITY OF TURNING SHALL BE LOCKED SECURELY IN PLACE BY DOUBLE NUTTING AT THE HANGER ROD ATTACHMENT TO THE STRUCTURE, AND AT THE PIPE HANGER.

NOM. PIPE SIZE-INCHES	MAX SPAN-FT	MIN. ROD SIZE-INCHI
1	7	3/8
1-1/2	9	3/8
2	10	3/8
3	12	1/2
4	14	5/8
c	17	7/1

- 3. ALL PIPE HANGERS AND EQUIPMENT SUPPORTS SHALL BE LOCATED A MINIMUM DISTANCE OF 2" FROM ANY REFRIGERANT
- 4. ALL PLUMBING FIXTURES CONNECTED TO A POTABLE WATER SYSTEM WITH HOSE CONNECTIONS ON THE OUTLET SIDE AND OWNER FURNISHED EQUIPMENT WITH DIRECT CONNECTIONS. SHALL BE PROVIDED WITH BACKFLOW PREVENTION.

15420 - DRAINAGE AND VENT SYSTEMS

- UNDERGROUND BUILDING DRAIN PIPE AND FITTINGS: A. NO HUB ABS OR PVC PLASTIC PIPE AND FITTINGS PER ASTM D2661 WITH ASTM D2235 SOLVENT
 - ASTM A74 SERVICE WEIGHT, HUB AND SPIGOT CAST IRON SOIL PIPE, OR ASTM A888 (OR CISPI 301) HUBLESS CAST IRON SOIL PIPE WITH ASTM C564 HEAVY DUTY SHIELDED STAINLESS STEEL COUPLINGS.
 - C. NO ASTM D2729 PIPE SHALL USED UNDERGROUND.
- ABOVE GROUND SANITARY DRAINAGE AND VENT PIPING, IN ALL AREAS EXCEPT AIR PLENUMS AND EXCEPT IN A FIRE RATED BUILDING, SHALL BE ABS TYPE DWV PLASTIC PIPE AND FITTINGS PER ASTM D2661 WITH ASTM D2255 SOLVENT, OR PVC PLASTIC PIPE AND FITTINGS PER ASTM D2665 WITH ASTM D2564 SOLVENT, OR SERVICE WEIGHT, NO HUB CAST IRON COUPLED PIPE AND FITTINGS WITH COMPRESSION TYPE NEOPRENE GASKETS AND STAINLESS STEEL BANDS.
- ALL SANITARY DRAINAGE AND VENT PIPING INSIDE AIR PLENUMS AND ANYWHERE IN A FIRE RATED BUILDING SHALL BE NO HUB SERVICE WEIGHT CAST IRON COUPLED PIPE AND FITTINGS WITH COMPRESSION TYPE NEOPRENE GASKETS AND STAINLESS STEEL BANDS. ASTM B306 COPPER PIPE MAY BE USED WITH SOLDERED JOINTS FOR PIPE 3" AND SMALLER.
- ABOVE GROUND ROOF DRAIN LINES, EXCEPT IN AIR PLENUMS AND ANYWHERE IN A FIRE RATED BUILDING, SHALL BE ABS TYPE DWV PLASTIC PIPE AND FITTINGS PER ASTM D2661 WITH ASTM D2255 SOLVENT, OR PV C PLASTIC PIPE PER ASTM D2665 WITH ASTM D2564 SOLVENT.
- INSTALL SANITARY DRAIN LINES 2-1/2" AND LESS WITH A SLOPE OF 2%. INSTALL SANITARY DRAIN LINES 3"-6" WITH A SLOPE OF NOT LESS THAN 1%.

PLUMBING SPECIFICATIONS

15420 - DRAINAGE AND VENT SYSTEMS

11. CLEANOUTS

- A. FINISHED WALL CLEANOUTS: SMITH FIGURE 4472 COMPLETE WITH CAST BRONZE TAPER THREADED PLUG, STAINLESS STEEL COVER AND SCREW.
- FLOOR CLEANOUTS (UNFINISHED AREAS): SMITH FIGURE 4223 DUCO CAST IRON CLEANOUT WITH ROUND ADJUSTABLE SCORIATED SECURED CAST IRON TOP, TAPER THREADED BRONZE PLUG AND SPIGOT OUTLET.
- FINISHED FLOOR CLEANOUTS (CONCRETE FLOORS): SMITH FIGURE 4023 DUCO CAST IRON CLEANOUT WITH ADJUSTABLE SCORIATED SECURED NICKEL BRONZE TOP, TAPER THREADED
- CAST BRONZE PLUG AND SPIGOT OUTLET. FINISHED FLOOR CLEANOUTS (CARPETED FLOORS): SMITH FIGURE 4023-Y SAME AS CONCRETE FLOORS WITH CARPET
- E. FINISHED FLOOR CLEANOUTS (TILE FLOORS): SMITH FIGURE 4163 DUCO CAST IRON CLEANOUT WITH SQUARE ADJUSTABLE SECURED NICKEL BRONZE TOP WITH 1/8" RECESS. TAPER
- THREADED BRONZE PLUG AND SPIGOT OUTLET. F. EXTERIOR CLEANOUTS (CLEANOUT TO GRADE): SMITH FIGURE 4253 DUCO CAST IRON CLEANOUT AND DOUBLE FLANGED HOUSING WITH HEAVY DUTY SECURED SCORIATED CAST IRON COVER WITH LIFTING DEVICE, TAPER THREADED BRONZE PLUG AND SPIGOT OUTLET.
- 12. FLOOR DRAINS:
 - D-1 FLOOR DRAIN: SMITH FIGURE 2010-BP CAST IRON BODY AND FLASHING COLLAR WITH PROTECTIVE CAP AND SQUARE NICKEL BRONZE ADJUSTABLE STRAINER HEAD WITH SECURED SQUARE HOLE GRATE, AND TRAP PRIMER CONNECTION.

15440 - PLUMBING FIXTURES

- PROVIDE AND INSTALL CARRIERS AS REQUIRED FOR FLOOR OR WALL MOUNTED PLUMBING FIXTURES. INSTALL ALL FIXTURES WITH ACCESSORIES AS REQUIRED TO PROVIDE A COMPLETE. WORKABLE INSTALLATION.
- 2. PLUMBING FIXTURES SHALL INCLUDE COMPRESSION STOPS ABOVE FLOOR IN SUPPLIES TO ALL FIXTURES AND A MINIMUM 17 GAUGE P-TRAP.
- 3. ALL LAVATORIES AND HAND SINKS WILL HAVE A COMBINATION FAUCET OR PREMIXING FAUCET CAPABLE OF SUPPLYING WARM WATER FOR A MINIMUM OF 10 SECONDS.
- 4. ALL JANITORIAL SINK FAUCETS MUST BE PROVIDED WITH AN APPROVED BACKFLOW PREVENTION DEVICE.

15460 - WATER HEATERS

- INSTALL UNITS PLUMB AND LEVEL AND FIRMLY ANCHORED PER SEISMIC REQUIREMENTS, MAINTAIN MANUFACTURER'S RECOMMENDED CLEARANCES. ORIENT SO CONTROLS AND DEVICES NEEDING SERVICING ARE ACCESSIBLE.
- 2. CONNECT HOT AND COLD WATER PIPING TO UNITS WITH SHUT-OFF VALVES AND UNIONS. CONNECT HOT WATER CIRCULATING PIPING TO UNIT WITH SHUT-OFF VALVE, CHECK VALVE AND UNION.
- 3. USE DIELECTRIC FITTINGS AND UNIONS WHERE PIPING CONNECTIONS ARE DISSIMILAR METALS.
- 4. INSTALL VACUUM RELIEF VALVE IN COLD WATER INLET PIPING. EXTEND RELIEF VALVE DISCHARGE TO CLOSEST FLOOR DRAIN. INSTALL DRAIN AS INDIRECT WASTE TO SPILL INTO OPEN DRAIN OR OVER FLOOR DRAIN.
- PROVIDE AND INSTALL EXPANSION TANK AS SCHEDULED IN DRAWINGS. EXPANSION TANK: DIAPHRAGM TYPE, PRE- PRESSURIZED STEEL TANK WITH RELIEF VALVE SETTING @ 120 PSI MAXIMUM PRESSURE.
- 6. ELECTRICAL CONNECTIONS: POWER WIRING AND DISCONNECT SWITCHES ARE SPECIFIED IN DIVISION 16. CONNECT UNIT COMPONENTS TO GROUND IN ACCORDANCE WITH THE NATIONAL ELECTRICAL CODE.

DEFINITIONS

NOTE: ALL DEFINITIONS MAY NOT BE USED

INDICATED: THE TERM "INDICATED" REFERS TO GRAPHIC REPRESENTATIONS, NOTES, OR SCHEDULES ON THE DRAWINGS, OTHER PARAGRAPHS OR SCHEDULES IN THE SPECIFICATIONS, AND SIMILAR REQUIREMENTS IN THE CONTRACT DOCUMENTS. WHERE TERMS SUCH AS "SHOWN", "NOTED", "SCHEDULED", AND "SPECIFIED" ARE USED. IT IS TO HELP THE READER LOCATE THE REFERENCE, NO LIMITATION ON LOCATION IS INTENDED.

DIRECTED: TERMS SUCH AS "DIRECTED", "REQUESTED", AUTHORIZED", "SELECTED", "APPROVED", "REQUIRED", AND "PERMITTED" MEAN "DIRECTED BY THE ENGINEER", "REQUESTED BY THE ENGINEER", AND SIMILAR PHRASES.

APPROVE: THE TERM "APPROVED", WHERE USED IN CONJUNCTION WITH THE ENGINEER'S ACTION ON THE CONTRACTOR'S SUBMITTALS, APPLICATIONS, AND REQUESTS, IS LIMITED TO THE ENGINEER'S DUTIES AND RESPONSIBILITIES AS STATED IN GENERAL AND SUPPLEMENTARY CONDITIONS.

FURNISH: THE TERM "FURNISH" IS USED TO MEAN "SUPPLY AND DELIVER TO THE PROJECT SITE, READY FOR UNLOADING, UNPACKING, ASSEMBLY, INSTALLATION, AND SIMILAR OPERATIONS."

INSTALL: THE TERM "INSTALL" IS USED TO DESCRIBE OPERATIONS AT PROJECT SITE INCLUDING THE ACTUAL "UNLOADING, UNPACKING, ASSEMBLY, ERECTION, PLACING, ANCHORING, APPLYING, WORKING TO DIMENSION, FINISHING, CURING, PROTECTING, CLEANING, AND SIMILAR OPERATIONS TO MAKE THE ITEM FULLY OPERATIONAL

PROVIDE: THE TERM "PROVIDE" MEANS "TO FURNISH AND INSTALL, COMPLETE AND READY FOR THE INTENDED USE."

INSTALLER: AN "INSTALLER" IS THE CONTRACTOR OR AN ENTITY ENGAGED BY THE CONTRACTOR, EITHER AS AN EMPLOYEE. SUBCONTRACTOR, OR SUB-SUBCONTRACTOR, FOR PERFORMANCE OF A PARTICULAR CONSTRUCTION ACTIVITY, INCLUDING INSTALLATION. ERECTION, APPLICATION, AND SIMILAR OPERATIONS. INSTALLERS ARE REQUIRED TO BE EXPERIENCED IN THE OPERATIONS THEY ARE ENGAGED TO PERFORM.

SYMBOL LEGEND DESCRIPTION SYMBOL PLUMBING PIPING SOIL. WASTE - ABOVE GRADE SOIL, WASTE - BELOW GRADE ______ ACID WASTE - BELOW GRADE COLD WATER _____ HOT WATER VTR VENT THRU ROOF **EXISTING PIPE** VALVES, METERS, AND GAUGES SHUT OFF VALVE BALL VALVE PLUMBING SYMBOLS FLOOR CLEANOUT REFERENCE AND LINE SYMBOLS DETAIL INDICATOR: # INDICATES DETAIL NUMBER, SHEET INDICATES DRAWING SHEET SHEET/ WHERE DETAIL IS SHOWN. 100 ROOM OR SPACE NUMBER. KEYNOTE INDICATOR. REVISION INDICATOR. CU-1EQUIPMENT INDICATOR. (P-PLUMBING FIXTURE INDICATOR. —\/,— BREAK, STRAIGHT BREAK, ROUND. HIDDEN FEATURES LINE: HIDDEN, THIN LINE. _____ CONTRACT LIMIT LINE: DASHDOT, WIDE LINE. **—** : **—** : **—** NEW CONNECTION POINT TO FXISTING

ABBREVIATIONS

	NOTE: ALL ABBREVIATI	ONS MAY	NOT BE USED
AD	ACCESS DOOR	MCA	MINIMUM CIRCUIT AMPS
AIR	AIR CONDITION(-ING,-ED)	MFR	MANUFACTURER
COND		MIŅ	MINIMUM
APD	AIR PRESSURE DROP	N/A	NOT APPLICABLE
3D	BALANCING DAMPER	NC	NORMALLY CLOSED
3HP	BRAKE HORSE POWER	NC NIC	NOISE CRITERIA
3TU 3TUH	BRITISH THERMAL UNIT BTU/HOUR	NIC NO	NOT IN CONTRACT NORMALLY OPEN
CFH	CUBIC FEET PER HOUR	NPSH	NET POSITIVE SUCTION
CFM	CUBIC FEET PER MINUTE	141 311	HEAD
CLG	COOLING	NTS	NOT TO SCALE
COMP	COMPONENT	OA	OUTSIDE AIR
COND	CONDENS(-ER, -ING,	OD	OUTSIDE DIAMETER
	-ATION)	OZ	OUNCE
CV	CONTROL VALVE	PD	PRESSURE DROP OR
CW	COLD WATER	D.C	DIFFERENCE
DIA DISCH	DIAMETER DISCHARGE	PG PH	PROPYLENE GLYCOL PHASE
DP DP	DEPTH OR DEEP	PPM	PARTS PER MILLION
OB	DRY BULB TEMPERATURE	PRESS	PRESSURE
(E)	EXISTING	PSF	POUNDS PER SQUARE
EER	ENERGY EFFICIENCY RATIO		FOOT
	EFFICIENCY	PSI	POUNDS PER SQUARE
ΞG	ETHYLENE GLYCOL		INCH
ELEC	ELECTRIC	PSIA	PSI ABSOLUTE
ELEV	ELEVATION	PSIG	PSI GAUGE
ENT	ENTERING	R	THERMAL RESISTANCE
EVAP	EVAPORAT(-E, -ING, -ED, -OR)	RA RECIRC	RETURN AIR RECIRCULATE
EWT	ENTERING WATER	REFR	REFRIGERATION
_ ** '	TEMPERATURE	REQD	REQUIRED
EXT	EXTERNAL	RLA	RATED AMPS
(F)	FUTURE	RPM	REVOLUTIONS PER MINUTE
-	FAHRENHEIT	RW	RAINWATER
FC	FLEXIBLE CONNECT(-OR,	SA	SUPPLY AIR
-D	-ION) FIRE DAMPER	SC SCFM	SHADING COEFFICIENT STANDARD CUBIC FEET
FLA	FULL LOAD AMPS	SCI W	PER MINUTE
-PI	FINS PER INCH	SCW	SOFT COLD WATER
	FEET PER MINUTE	SF	SAFETY FACTOR
	FEET PER SECOND	SH	SENSIBLE HEAT
FSD	FIRE SMOKE DAMPER	SL	SEA LEVEL
=T	FEET (CALL CALL)	SP SPECIAL	STATIC PRESSURE
GAL	GALLON(S)		SPECIFICATION(S)
GPH GPM	GALLONS PER HOUR GALLONS PER MINUTE	SQ STD	SQUARE STANDARD
JP MI HD	HEAD	STM	STEAM
iG	MERCURY	TEMP	TEMPERATURE
HR	HOUR	TD	TEMP. DROP OR DIFF.
ΗT	HEIGHT	THERM	THERMAL
HTG	HEATING	TOT	TOTAL
HP.	HORSE POWER	TSTAT	THERMOSTAT
HW	HOT WATER	V	VOLT
∃Z D	HERTZ(FREQUENCY) INSIDE DIAMETER	VAC VAV	VACUUM VARIABLE AIR VOLUME
N	INCH	VEL	VELOCITY
.∵ ≺W	KILOWATT	VENT	VENT, VENTILATION
_AT	LEAVING AIR	VERT	VERTICAL
	TEMPERATURE	VFD	VARIABLE FREQUENCY
_BS	POUNDS		DRIVE
_G	LENGTH	VOL	VOLUME
	LATENT HEAT LOCKED ROTOR AMPS	WC WG	WATER COLUMN WATER GAUGE
	LEAVING	WG WPD	WATER GAUGE WATER PRESSURE DROP
_VG _WT	LEAVING WATER	WFD	WATER PRESSURE DROP
	TEMPERATURE	WT	WEIGHT
MAX	MAXIMUM	WB	WET BULB TEMP
мвн	THOUSAND BTU PER HOUR	YR	YEAR

PLUMBING PIPING GENERAL NOTES

BE PLASTIC COATED.

- 1. PROVIDE PROPER PROVISIONS FOR EXPANSION, CONTRACTION, OR MOVEMENT OF ALL PIPING.
- 2. PROVIDE LARGE ENOUGH PIPE SLEEVES THROUGH WALL OR FLOOR TO ALLOW FOR ANTICIPATED DIFFERENTIAL MOVEMENT.
- ALL PIPING SHALL BE SUPPORT WITH CLEVIS HANGERS (MSS TYPE 1). PERFORATED METAL STRAPS OR PLASTIC STRAPPING (PLUMBER TAPE)
- SHALL NOT BE USED TO SUPPORT OR BRACE ANY PIPE. 4. PROVIDE PIPE HANGERS WITHIN 18-INCHES OF ALL CHANGES OF
- DIRECTION.

5. PROVIDE SWAY BRACING FOR ALL PIPING 4" AND LARGER AT ALL

- CHANGES IN DIRECTION GREATER THAN 45-DEGREES. ALL STEEL CLEVIS HANGERS USED TO SUPPORT COPPER PIPING SHALL BE COPPER PLATED OR PLASTIC COATED.
- 7. ALL STEEL CLEVIS HANGERS USED TO SUPPORT PLASTIC PIPING SHALL
- 8. COPPER PIPING SHALL NOT COME IN CONTACT WITH FIRE TREATED LUMBER. PROVIDE 1/2" THICK SLIP-ON CLOSED CELL INSULATION WHERE COPPER PIPING IS ADJACENT TO FIRE TREATED LUMBER. CLOSED CELL INSULATION SHALL EXTEND A MINIMUM OF 1-1/2" PAST LUMBER.
- ALL EXPOSED PIPING SHALL INSTALLED IN A NEAT ARRANGED PARALLEL TO THE BUILDING TO BUILDING STRUCTURE.
- 10. ALL EXPOSED DOMESTIC WATER PIPE IN OCCUPIED SPACES SHALL BE POLISHED CHROME PLATED.
- 11. ALL EXPOSED DRAINAGE PIPING IN OCCUPIED SPACES INCLUDING TRAPS UNDER SINKS SHALL BE POLISHED CHROME PLATED.
- 12. DRAWINGS SHOWS GENERAL ARRANGEMENT OF THE DRAIN WASTE AND VENT SYSTEM WITH THE REQUIRED CLEANOUTS. CONTRACTOR SHALL PROVIDE ALL ADDITIONAL CLEANOUTS AS REQUIRED BY THE PLUMBING
- 13. ALL VENTS THROUGH ROOF SHALL BE A MINIMUM OF 25 FEET FROM ANY AIR INTAKE.
- 14. ALL SANITARY DRAINAGE AND WASTE SYSTEM SMALLER THAN 3" SHALL BE SLOPED IN DIRECTION OF FLOW AT A MINIMUM OF 1/4" PER FOOT.
- 15. ALL ROOF DRAINAGE PIPING SHALL BE SLOPED IN DIRECTION OF FLOW AT A MINIMUM OF 1/8" PER FOOT.

PLUMBING GENERAL NOTES

1. THE PLUMBING DRAWINGS SHOW THE GENERAL DESIGN, ARRANGEMENT

AND EXTENT OF THE PLUMBING SYSTEM. BECAUSE OF THE SMALL SCALE

OF THE DRAWINGS, THESE DRAWINGS DO NOT SHOW ALL OFFSETS, BENDS

OR ELBOWS NECESSARY FOR THE COMPLETE INSTALLATION IN THE SPACE

PROVIDED. CONTRACTOR SHALL MAKE SUCH SLIGHT ALTERATIONS AS

MAJOR DEVIATIONS SUCH AS CHANGES IN COMPONENT SIZES, WEIGHTS,

SUPPLEMENT EACH OTHER AND SHALL BE INTERPRETED AS IN INTEGRAL

FURNISHED AND INSTALLED AS THOUGHT SHOWN AND CALLOUT IN BOTH.

APPLICABLE CITY, COUNTY, STATE, AN FEDERAL CODES AN REGULATIONS

QUANTITIES OR MATERIAL REQUIRE PRIOR APPROVAL BY THE DESIGN

UNIT WITH THE ITEMS SHOWN ON ONE AND NOT THE OTHER BEING

REQUIREMENTS OF THE MOST RECENTLY ADOPTED BUILDING CODES, MECHANICAL CODE, PLUMBING CODE, ELECTRICAL CODE, AND ALL OTHER

4. THE ENTIRE PLUMBING INSTALLATION SHALL CONFORM TO ANY CODES.

RULES, REGULATIONS AND REQUIREMENTS OF THE BUILDING OWNER.

THE CONTRACTOR SHALL COORDINATE THE INSTALLATION OF ALL

THEY SHALL BE RESOLVED PRIOR TO INSTALLATION.

INFORMATION ON ALL OTHER CONSTRUCTION DOCUMENT.

SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.

SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.

PLUMBING COVER SHEET

PLUMBING SCHEDULES

SHEET NO SHEET TITLE

P.001

P.101

P.601

5. PRIOR TO FABRICATION AND INSTALLATION OF ANY PLUMBING COMPONENT

6. ALL PLUMBING INFORMATION IS NOT SHOWN ON THE PLUMBING DRAWINGS.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING ALL

7. THE CONTRACTOR SHALL BE RESPONSIBLE TO REVIEW AND USE, WHERE

APPROPRIATE, ALL THE PLUMBING DETAILS SHOWN ON THE DRAWINGS.

SYMBOLS OR KEYED NOTES. ANY CHANGES RESULTING FROM FAILURE TO

INSTALL THE PLUMBING SYSTEM WITHOUT USING THE INCLUDED DETAILS

CONNECTIONS TO ALL PLUMBING EQUIPMENT. THE PIPING SCHEMATICS

FITTINGS, GAUGES, ETC. ANY CHANGES RESULTING FROM FAILURE TO

INSTALL THE PLUMBING SYSTEM WITHOUT USING THE INCLUDED DETAILS

SHOW DETAILED CONNECTIONS INCLUDING ALL NECESSARY VALVES,

9. ANY PART OF THE PLUMBING INSTALLATION THAT FAILS, IS UNFIT, OR

BECOMES DAMAGED DURING CONSTRUCTION SHALL BE REPAIRED OR

REPLACES BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER.

PLUMBING SHEET INDEX

PLUMBING FLOOR PLAN AND ISOMETRICS

DETAILS MAY OR MAY NOT BE CALLED OUT ON THE DRAWINGS WITH

8. THE CONTRACTOR SHALL BE RESPONSIBLE TO REVIEW AND USE THE

PIPING SCHEMATICS INCLUDED WITH THE DRAWINGS FOR PIPING

PLUMBING WORK WALL ALL OTHER BUILDING TRADES, INCLUDING BUILDING

TRADES HIRED DIRECTLY BY THE OWNER. WHERE CONFLICTS MAY OCCUR,

2. THE DRAWINGS AND SPECIFICATIONS HAVE BEEN PREPARED TO

3. THE ENTIRE PLUMBING INSTALLATION SHALL CONFORM TO THE

MAY BE NECESSARY TO MAKE THE SYSTEM COMPLETE AND OPERATIONAL

16. SLOPE VENT SYSTEM TOWARDS DRAINAGE SYSTEM.

IN ACCORDANCE WITH THE DESIGN INTENT.

IN EFFECT.

PLUMBING FIXTURE & EQUIPMENT NOTES

- 1. SIMILAR EQUIPMENT SHALL BE OF THE SAME MANUFACTURER.
- 2. ALL EQUIPMENT SHALL PROVIDE THE SCHEDULED PERFORMANCE AT THE JOB SITE ELEVATION.
- 3. FIXTURE AND EQUIPMENT MODEL NUMBERS SHOWN IN PLUMBING FIXTURE SCHEDULE AND PLUMBING EQUIPMENT SCHEDULE ARE SHOWN TO ESTABLISH THE TYPE OF PRODUCT THAT SHALL BE USED. THE SELECTED PRODUCT SHALL MEET THE SCHEDULED PERFORMANCE DATA SHOWN ON THE SCHEDULE EVEN IF A DIFFERENT MODEL IS SUPPLIED THAT IS DIFFERENT THAN THAT SCHEDULED.
- 4. ALL EQUIPMENT SHALL BE INSTALLED IN STRICT ACCORDANCE WITH THE EQUIPMENT MANUFACTURER'S INSTALLATION INSTRUCTIONS. PROVIDE ALL NECESSARY FITTINGS, TRANSITIONS, VALVES AND OTHER DEVICES AND ACCESSORIES REQUIRED FOR A COMPLETE, WORKABLE INSTALLATION.
- 5. ALL MOTOR STARTING EQUIPMENT, NOT PROVIDES AS A PART OF THE PLUMBING EQUIPMENT. SHALL BE PROVIDE BY DIVISIONS 16.
- 6. SEE "PLUMBING FIXTURE SCHEDULE" FOR INDIVIDUAL TRAPS, WASTE, VENT, AND DOMESTIC WATER PIPING FOR INDIVIDUAL FIXTURES.
- 7. ALL PLUMBING EQUIPMENT SHALL BE LISTED AND LABELED BY AN APPROVED TESTING AGENCY.
- 8. FIXTURES, EQUIPMENT AND PIPING INSTALLATION SHALL MEET NSF
- 9. PROVIDE WATER HAMMER ARRESTERS (WHA-A) AT ALL PIPING CONNECTIONS TO PLUMBING FIXTURES AND PLUMBING EQUIPMENT PROVIDED WITH QUICK CLOSING VALVE AND INSTALLATIONS WHICH RESULT IN EXCESS PIPE VIBRATION OR MOVEMENT
- 10. ALL OWNER FURNISHED EQUIPMENT WITH DIRECT CONNECTION TO THE DOMESTIC WATER SYSTEM SHALL BE PROVIDED WITH AN APPROVED BACKFLOW DEVICE.
- 11. INSTALLATION AND FINAL CONNECTION OF ALL OWNER FURNISHED EQUIPMENT SHALL BE BY DIVISION 15.

PLUMBING PIPE TESTING

PRESSURE OF TEN (10) FEET OF HEAD FOR 15 MINUTES.

PRESSURE AT 125 PSIG FOR 15 MINUTES.


2. DOMESTIC WATER SYSTEM DOWN STREAM OF BUILDING PRESSURE

DRAIN WASTE AND VENT SYSTEM: ALL SECTIONS OF DRAIN WASTE AND

VENT SYSTEM SHALL BE PRESSURE TESTED WITH WATER AT A MINIMUM

REDUCING STATION: ALL SECTIONS OF THE DOMESTIC WATER SYSTEM

SHALL BE PRESSURE TESTED WITH POTABLE WATER AT A MINIMUM



SYMMETRY FIRST ARCHITECTS,

8600 Foundry Street Box 2069 Savage, MD 20763 240-568-0700 240-568-0354 fax

www.symmetryfirst.com

STAMP

PROFESSIONAL CERTIFICATION: I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF LICENSE NO. 38508 EXPIRATION DATE: MARCH 03, 2012

NOTE: THESE DRAWINGS ARE THE PROPERTY

OF SYMMETRY FIRST ARCHITECTS, LLC AND, AS SUCH, MAY NOT BE REPRODUCED OR RE-USED EITHER WHOLLY OR IN PART, WITHOUT PRIOR WRITTEN CONSENT OF SYMMETRY FIRST ARCHITECTS, LLC.

PROJECT PHASE BID IDOCUMENTSI

PROJECT TITLE

A.D.C.**TENANT** BUILD-OUT

2001COMMERCE PARK DR. SUITE 2001-B ANNAPOLIS, MD 21401

	REVISIONS				
SYMBOL	DATE	ISSUED FOR			
Λ	10.21.11	PERMIT REVISION			

PROJECT NUMBER DATE

AS NOTED **SCALE**

11-160

9.1.11

DRAWING TITLE **PLUMBING**

COVER SHEET

SHEET NUMBER

P.00 I